BRUHAT BANGALORE MAHANAGAR PALIKE

Project Division, Yelahanka Zone

163

NEGOTIATED SCHEDULE - B

Issued to C. N. S. Murthy.

Tender Number BBMP/2016-17/BD/WORK_INDENT21513

Tender Name Construction of Additional Class rooms, toilet and Auditorium and Providing office accessories to Yelahanka Government Degree college Yelahanka Bangalore in ward No.01

SNo	Item Name	Unit	Estimate Quantity	Negotiated Rates quoted by Sri. MURTHY C N S	
				Rate in figures	Rate in words
1	ADDITIONAL CLASS ROOMS AND STAIRCASE EASTERN SIDE - Dismantling of existing structures like culverts,bridges, retaining walls and other structure comprising of masonry, cementconcrete, wood work, steel work, including T&P and scaffolding wherevernecessary, sorting the dismantled material, disposal of unserviceablematerial and stacking the serviceable material with all lifts complete asper specifications Dismantling brick/Tile work B. In cement mortar.	Cum	45.14	275.00	Rs Two hundred Seventy five only.
2	Dismantling of existing structures like culverts,bridges, retaining walls and other structure comprising of masonry,cement concrete, wood work, steel work, including T&P and scaffoldingwherever necessary, sorting the dismantled material, disposal ofunserviceable material and stacking the serviceable material with all liftscomplete as per specifications Lime /Cement Concrete. I. By Manual Means .B. Cement Concrete Grade M-15 & M-20.	Cum	6.85	420.00	Rs Four hundred twenty only.
3	Dismantling of existing structures like culverts,bridges, retaining walls and other structure comprising of masonry,cement concrete, wood work, steel work, including T&P and scaffoldingwherever necessary, sorting the dismantled material, disposal ofunserviceable material and stacking the serviceable material with all liftscomplete as per specifications.Prestressed / Reinforced cement concrete grade M-20 & above.	Cum	6.85	1145.00	Rs One thousand one hundred Forty five only.
4	Dismantling cement concrete flooring or plain cement concrete work including removing and conveying the debris to distance upto 200m (within average thickness of 15 cms).	Sqm	45.66	61.00	Rs Sixty one only

SNo	Item Name	Unit	Estimate Quantity	Negotiated Rates quoted by Sri. MURTHY C N S	
				Rate in figures	Rate in words
5	Dismantling of existing structures like culverts,bridges, retaining walls and other structure comprising of masonry, cementconcrete, wood work, steel work, including T&P and scaffolding wherevernecessary, sorting the dismantled material, disposal of unserviceablematerial and stacking the serviceable material with all lifts complete asper specifications.Rubble stone masonry in cement mortar.	Cum	6.23	275.00	Rs Two hundred Seventy five only
6	Earthwork in surface excavation in ordinary soil for levelling and lowering the ground manually (other than foundation of buildings, culverts, road drains and trenches of pipe lines and cables)and removing the excavated stuff to a distance not exceeding 50mand lift upto 1.5m, excavated surface levelled and neatly dressed, disposed earth to be levelled after breaking of clods and neatly dressed as per specifications.	Cum	43.64	176.00	Rs one hundred Seventy Six only
7	Earth work excavation for foundation of buildings, water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, in Hard soil not exceeding 1.5m in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50m after breaking of clods complete as per specification	Cum	33.22	317.00	Rs Three hundred Seventeen only
8	Providing and laying in position plain cement concrete of mix 1:3:6 with OPC cement @ 220kgs, with 40mm and down size graded granite metal coarse aggregate @ 0.892cum and fine aggregates @ 0.465cum machine mixed, machinemixed, concrete laid in layers not exceeding 15 cms, thick well compacted in foundation and plinth, cost of all materials, labour HOM of machinery, curing complete as per specifications.	Cum	3.57	5754.00	Rs Five thousand Seven hundred fifty four only
9	Providing and constructing granite / trap / basalt Size Stone Masonry in cement mortar 1:6, stone hammered dressed in courses not less than 20 cms high, bond stones at two m. apart in each course including cost of maerials, labour, curing Complete as per specifications.	Cum	3.73	4544.00	Rs Four thousand five hundred forty four only
10	Filling available excavated earth (excluding rock) insides of foundations upto plinth in layers not exceeding 20cms. In depth, compacting each deposited layer by ramming after watering with a lead upto 50m. And lift upto 1.5m including cost of all labour complete as per specifications.	Cum	13.29	142.00	Rs one hundred forty two only
11	Transportation of excavated earth by mechanical means including loading and unloading with a lead of 20 kmtr and dispersing the same as directed.	Cum	19.93	128.00	Rs one hundred twenty Eight only.

Signature of the Contractor

Executive Engineer (Project)

SNo	Item Name	Unit	Estimate Quantity	Negotiated Rates quoted by Sri. MURTHY C N S	
				Rate in figures	Rate In words
12	Providing and removing Centering, shuttering, strutting, propping etc.,and removal of from work for foundations,footings,bases of columns for mass concrete incxluding cost of all materials, labour complete as per specification	Sqm	21.60	268.00	Rs Two hundred Sixty Eight only
13	Providing and laying in position reinforced cement concrete of design mix M25 with OPC cement @ 340kgs, with 20mm and down size graded granite metal coarse aggregates @0.70cum and fine aggregtes @ 0.47cum, with superplastisiser @3lts confirming to IS9103-1999 Reaffirmed-2008, machine mixed, concrete laid in layers not exceeding 15 cms thick, vibrated for all works in foundation plinth for roof slabs, staircase, lintles, retaining walls, return walls, walls (any thickness) including attached plasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window cills, fillets etc., including cost of all materials, labour, HOM of machinery, curing, complete as per specifications.	Cum	8.83	7208.00	Rs Seven thousand two hundred Eight only
14	Providing and laying in position reinforced cement concrete of design mix M25 with OPC cement @ 340kgs, with 20mm and down size graded granite metal coarse aggregates @0.70cum and fine aggregtes @ 0.47cum, with superplastisiser @3lts confirming to IS9103-1999 Reaffirmed-2008, machine mixed, concrete laid in layers not exceeding 15 cms thick, vibrated for all works in ground floor level for roof slabs, staircase, lintles, retaining walls, return walls, walls (any thickness) including attached plasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window cills, fillets etc., including cost of all materials, labour, HOM of machinery, curing, complete as per specifications. Ground Floor	Cum	9.74	7208.00	Rs Seven thousand two hundred Eight only
15	Providing and laying in position reinforced cement concrete of design mix M25 with OPC cement @ 340kgs, with 20mm and down size graded granite metal coarse aggregates @0.70cum and fine aggregtes @ 0.47cum, with superplastisiser @3lts confirming to IS9103-1999 Reaffirmed-2008, machine mixed, concrete laid in layers not exceeding 15 cms thick, vibrated for all works in ground floor level for roof slabs, staircase, lintles, retaining walls, return walls, walls (any thickness) including attached plasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window cills, fillets etc., including cost of all materials, labour, HOM of machinery, curing, complete as per specifications. First Floor	Cum	7.38	7267.00	Rs Seven thousand two hundred Sixty Seven only

Signature of the Contractor

Executive Engineer (Project)

SNo	Item Name	Unit	Estimate Quantity	Negotiated Rates quoted by Sri. MURTHY C N S	
				Rate in figures	Rate in words
16	Providing and laying in position reinforced cement concrete of design mix M25 with OPC cement @ 340kgs, with 20mm and down size graded granite metal coarse aggregates @0.70cum and fine aggregtes @ 0.47cum, with superplastisiser @3lts confirming to IS9103-1999 Reaffirmed-2008, machine mixed, concrete laid in layers not exceeding 15 cms thick, vibrated for all works in ground floor level for roof slabs, staircase, lintles, retaining walls, return walls, walls (any thickness) including attached plasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window cills, fillets etc., including cost of all materials, labour, HOM of machinery, curing, complete as per specifications. Second Floor	Cum	7.38	7327.00	Rs Seven thousand three hundred twenty Seven only
17	Providing and laying cement concrete using 20mm and down size granite coarse aggregates and fine aggregares of ready mixed concrete for RCC works laid in 15 cms thick layers and well compated including vibrating, curing,etc., with all lead and lifts etc complete(excluisive of cost of steel and fabrication charges) Ready Mixed Cement Concrete for Beams, Staircase and Roof with M-25	Cum	45.10	7177.00	Rs Seven thousand one hundred Seventy Seven only
18	Providing and laying in position reinforced cement concrete of design mix M20 with OPC cement @ 24kgs, with 12mm and down size graded granite metal coarse aggregates @0.5175cum and fine aggregtes @ 0.345cum, with superplastisiser @0.225lts, machine mixed, well compacted for plain chajja of 7.5 cms. average thickness, upto ground floor level, including cost of all materials, labour, HOM of machinery, finishing, curing, complete as per specifications. Ground Floor	Sqm	3.24	516.00	Rs Five hundred Sixteen only
19	Providing and laying in position reinforced cement concrete of design mix M20 with OPC cement @ 24kgs, with 12mm and down size graded granite metal coarse aggregates @0.5175cum and fine aggregtes @ 0.345cum, with superplastisiser @0.225lts, machine mixed, well compacted for plain chajja of 7.5 cms. average thickness, upto ground floor level, including cost of all materials, labour, HOM of machinery, finishing, curing, complete as per specifications. First Floor	Sqm	3.24	522.00	Rs Five hundred twenty two only

Signature of the Contractor

Executive Engineer (Project)

SNo	Item Name	Unit	Estimate Quantity	Negotiated Rates quoted by Sri. MURTHY C N S	
				Rate in figures	Rate in words
20	Providing and laying in position reinforced cement concrete of design mix M20 with OPC cement @ 24kgs, with 12mm and down size graded granite metal coarse aggregates @0.5175cum and fine aggregtes @ 0.345cum, with superplastisiser @0.225lts, machine mixed, well compacted for plain chajja of 7.5 cms. average thickness, upto ground floor level, including cost of all materials, labour, HOM of machinery, finishing, curing, complete as per specifications. Second Floor	Sqm	3.24	528.00	Rs Five hundred twenty Eight only
21	Providing and laying in Mat for RCC roof at below the steel for avoiding concrete cement slurry as per the requirement of Engineer incharge.	Sqm	243.00	73.00	Rs Seventy three only
22	Providing and removing Centering, shuttering, strutting, propping etc.,and removal of from work for vertical surface such as walls at any thickness including attched plasters, butresses, plinth cills and string courses cost of all materials, labour complete as per specification	Sqm	34.32	337.00	Rs Three hundred thirty Seven only
23	Providing and removing Centering, shuttering, strutting, propping etc., for columns, pillars, piers, abutments, post and struts, square / rectangular / polygon in plan including cost of materials, labour complete as per specification and directions of the Engineer in charge. Ground Floor	Sqm	34.20	421.00	Rs Four hundred twenty one only
24	Providing and removing Centering, shuttering, strutting, propping etc., for columns, pillars, piers, abutments, post and struts, square / rectangular / polygon in plan including cost of materials, labour complete as per specification and directions of the Engineer in charge. First Floor	Sqm	26.10	427.00	Rs Four hundred twenty Seven only
25	Providing and removing Centering, shuttering, strutting, propping etc., for columns, pillars, piers, abutments, post and struts, square / rectangular / polygon in plan including cost of materials, labour complete as per specification and directions of the Engineer in charge. Second Floor	Sqm	26.10	433.00	Rs Four hundred thirty three only
26	Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for flat surface such as roofs landings balconies and likes thickness upto 200 mm including cost of all materials labour complete as per specifications upto 3.5M from Ground level. Ground Floor	Sqm	62.33	362.00	Rs Three hundred Sixty two only
27	Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for flat surface such as roofs landings balconies and likes thickness upto 200 mm including cost of all materials labour complete as per specifications upto 3.5M from Ground level. First Floor	Sqm	62.33	368.00	Rs Three hundred Sixty Eight only.

Executive Engineer (Project)

SNo	Item Name	Unit	Estimate Quantity	Negotiated Rates quoted by Sri. MURTHY C N S	
				Rate in figures	Rate in words
28	Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for flat surface such as roofs landings balconies and likes thickness upto 200 mm including cost of all materials labour complete as per specifications upto 3.5M from Ground level. Second Floor	Sqm	62.33	374.00	Rs Three hundred Seventy four only
29	Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for sides and soffits of beams, beam haunchings, cantilever girders, bressumers and lintles exceeding 1 m in depth incluidng cost of all materials, labour complete as per specifications.Ground Floor	Sqm	50.06	297.00	Rs Two hundred Ninety Seven only
30	Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for sides and soffits of beams, beam haunchings, cantilever girders, bressumers and lintles exceeding 1 m in depth incluidng cost of all materials, labour complete as per specifications.First Floor	Sqm	50.06	303.00	Rs Three hundred Three only
31	Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for sides and soffits of beams, beam haunchings, cantilever girders, bressumers and lintles exceeding 1 m in depth incluidng cost of all materials, labour complete as per specifications.Second Floor	Sqm	50.06	309.00	Rs Three hundred Nine only.
32	Providing and removing centering, shuttering, strutting,propping etc., for chajjas,corbalsetc., including edges incluidng cost of all materials, labour complete as per specifications.Ground Floor	Sqm	3.24	312.00	Rs Three hundred twelve only
33	Providing and removing centering, shuttering, strutting,propping etc., for chajjas,corbalsetc., including edges incluidng cost of all materials, labour complete as per specifications.First Floor	Sqm	3.24	318.00	Rs Three hundred Eighteen only.
34	Providing and removing centering, shuttering, strutting,propping etc., for chajjas,corbalsetc., including edges incluidng cost of all materials, labour complete as per specifications.Second Floor	Sqm	3.24	324.00	Rs Three hundred twenty four only
35	Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for Stairs (excluding landing) except spiral staircase including cost of all materials, labour complete as per specificaiton.Ground Floor	Sqm	25.17	553.00	Rs Five hundred fifty three only
36	Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for Stairs (excluding landing) except spiral staircase including cost of all materials, labour complete as per specificaiton.First Floor	Sqm	25.17	559.00	Rs Five hundred fifty nine only
37	Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for Stairs (excluding landing) except spiral staircase including cost of all materials, labour complete as per specificaiton.Second Floor	Sqm	25.17	565.00	Rs Five hundred Sixty five only.

SNo	Item Name	Unit	Estimate Quantity	Negotiated Rates quoted by Sri. MURTHY C N S	
				Rate in figures	Rate in words
38	Providing TMT Steel Reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications.TMT Bars Fe 500. Ground Floor	MT	3.76	65188.00	Rs Sixty five thousand one hundred Eighty Eight only
39	Providing TMT Steel Reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications.TMT Bars Fe 500.First Floor	MT	2.35	65716.00	Rs Sixty five thousand Seven hundred Sixteen only
40	Providing TMT Steel Reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications.TMT Bars Fe 500.Second Floor	MT	2.19	66244.00	Rs Sixty Six thousand two hundred fifty four only
41	Providing and constructing precast concrete Solid Blocks with compressive strength not less than 3.5 Newton per sqm with cement mortar 1:4 masonry (quion, jamb, closer blocks) with Solid Concrete Blocks of size (40x20x20) cms confirming to I.S 2185/1965 in Superstructure including cost of all materials, labour charges, scaffolding, curing complete as per specifications. Ground Floor	Sqm	61.53	1119.00	Rs one thousand one hundred Nineteen only
42	Providing and constructing precast concrete Solid Blocks with compressive strength not less than 3.5 Newton per sqm with cement mortar 1:4 masonry (quion, jamb, closer blocks) with Solid Concrete Blocks of size (40x20x20) cms confirming to I.S 2185/1965 in Superstructure including cost of all materials, labour charges, scaffolding, curing complete as per specifications. First Floor	Sqm	61.53	1155.00	Rs one thousand one hundred fifty five only
43	Providing and constructing precast concrete Solid Blocks with compressive strength not less than 3.5 Newton per sqm with cement mortar 1:4 masonry (quion, jamb, closer blocks) with Solid Concrete Blocks of size (40x20x20) cms confirming to I.S 2185/1965 in Superstructure including cost of all materials, labour charges, scaffolding, curing complete as per specifications. Second Floor	Sqm	61.53	1190.00	Rs one thousand one hundred Ninty only

SNo	Item Name	Unit	Estimate Quantity	Negotiated Rates quoted by Sri. MURTHY C N S	
				Rate in figures	Rate in words
44	Providing 12mm thick cement plaster in single coat with cement mortar 1:3, to ceiling including rounding off corners wherever required smooth rendering,, Providing and removing scaffolding, including cost of materials, labour, lead, lift, curing complete as per specifications and direction of the Engineer in charge Providing Lime rendering for Plastering to Ceiling including cost of materials, labour, curing complete as per specification.	Sqm	148.50	246.00	Rs Two hundred fifty Six only
45	Flooring with 20mm thick polished shahabad slabs using cement mortar 1:6, 25mm thick over existing cement concrete bed or top of roof laid to line and level and jointed withcement slurry mixed with pigment to match the shade of the slab, including cost of materials, labour, curing, polishing complete as per specifications. Ground Floor	Sqm	75.92	1362.00	Rs one thousand three hundred sixty two only
46	Flooring with 20mm thick polished shahabad slabs using cement mortar 1:6, 25mm thick over existing cement concrete bed or top of roof laid to line and level and jointed withcement slurry mixed with pigment to match the shade of the slab, including cost of materials, labour, curing, polishing complete as per specifications. First Floor	Sqm	75.92	1364.00	Rs one thousand three hundred Sixty four only
47	Flooring with 20mm thick polished shahabad slabs using cement mortar 1:6, 25mm thick over existing cement concrete bed or top of roof laid to line and level and jointed withcement slurry mixed with pigment to match the shade of the slab, including cost of materials, labour, curing, polishing complete as per specifications. Second Floor	Sqm	75.92	1366.00	Rs one thousand three hundred Sixty Six only
48	Fixing of door frames in an exisying opening including embedding frame in floor and walls after cutting masonary for holdfasts for embedding holdfast in cement concrete 1:3:6 of 20mm and downsize granite metal painting two coats of coal tar to sides of frame,making good the damages to walls and floor as required and disposal of the debries with lead upto 50 m. including cost of materials, labour, complete as per specifications.	Sqm	3.00	1202.00	Rs one thousand two hundred two only
49	Providing Honne wood frames of doors, windows, clerestory windows, ventilators and other frames, wrought, framed or assembled including making plaster groves (excluding cost of cement concrete and side clamps), but including cost of materials, labour, HOM of machineries complete as per specifications	Cum	0.21	121793.00	Rs one Lakh twenty one thousand Seven hundred Ninety three only

Signature of the Contractor

Executive Engineer (Project)

SNo	Item Name	Unit	Estimate Quantity	Negotiated Rates quoted by Sri. MURTHY C N S	
				Rate in figures	Rate in words
50	Providing and fixing in position fully panelled Honne Wood shutters for doors, styles and rails of 40mm thick with bottom and lock rails 180mm wide top rail and styles 100mm wide as per drawing and panels of 25mm thick including cost of materials, labour, HOM of machineries Complete as per Specifications. Ground Floor	Sqm	1.90	5368.00	Rs Five thousand three hundred Sixty Eight only
51	Providing and fixing in position fully panelled Honne Wood shutters for doors, styles and rails of 40mm thick with bottom and lock rails 180mm wide top rail and styles 100mm wide as per drawing and panels of 25mm thick including cost of materials, labour, HOM of machineries Complete as per Specifications. First Floor	Sqm	1.90	5372.00	Rs Five thousand three hundred Seventy two only
52	Providing and fixing in position fully panelled Honne Wood shutters for doors, styles and rails of 40mm thick with bottom and lock rails 180mm wide top rail and styles 100mm wide as per drawing and panels of 25mm thick including cost of materials, labour, HOM of machineries Complete as per Specifications. Second Floor	Sqm	1.90	5376.00	Rs Five thousand three hundred Seventy Six only
53	Providing 18mm thick cement plaster in single coat with cement mortar 1:4, to brick masonry including rounding off corners wherver required smooth rendering, : Providing lime rendering for plastering to wall and ceiling and Providing and removing scaffolding, cost of materials, labour, curing complete as per specifications, direction of the Engineer in charge.for Inside.Ground Floor	Sqm	84.86	278.00	Rs Two hundred Seventy Eight only.
54	Providing 18mm thick cement plaster in single coat with cement mortar 1:4, to brick masonry including rounding off corners wherver required smooth rendering, : Providing lime rendering for plastering to wall and ceiling and Providing and removing scaffolding, cost of materials, labour, curing complete as per specifications, direction of the Engineer in charge.for Inside.First Floor	Sqm	84.86	284.00	Rs Two hundred Eighty four only
55	Providing 18mm thick cement plaster in single coat with cement mortar 1:4, to brick masonry including rounding off corners wherver required smooth rendering, : Providing lime rendering for plastering to wall and ceiling and Providing and removing scaffolding, cost of materials, labour, curing complete as per specifications, direction of the Engineer in charge.for Inside.Second Floor	Sqm	84.86	290.00	Rs Two hundred Ninety only
56	Providing 18mm thick cement plaster in single coat with cement mortar 1:4, to brick masonry including rounding off corners wherver required smooth rendering, : Providing and removing scaffolding, cost of materials, labour, curing complete as per specifications and direction of the Engineer in charge.for Outside Plastering. Ground Floor	Sqm	83.88	249.00	Rs Two hundred forty nine only

Signature of the Contractor

Executive Engineer (Project)

SNo	Item Name	Unit	Estimate Quantity	Negotiated Rates quoted by Sri. MURTHY C N S	
				Rate in figures	Rate in words
57	Providing 18mm thick cement plaster in single coat with cement mortar 1:4, to brick masonry including rounding off corners wherver required smooth rendering, : Providing and removing scaffolding, cost of materials, labour, curing complete as per specifications and direction of the Engineer in charge.for Outside Plastering. First Floor	Sqm	83.88	261.00	Rs Two hundred Sixty one only
58	Providing 18mm thick cement plaster in single coat with cement mortar 1:4, to brick masonry including rounding off corners wherver required smooth rendering, : Providing and removing scaffolding, cost of materials, labour, curing complete as per specifications and direction of the Engineer in charge.for Outside Plastering. Second Floor	Sqm	83.88	273.00	Rs Two hundred Seventy three only
59	Providing applying two coats of wall putty to inside plastered walls and ceiling using white cement putty. Scrapping and levelling the surface using steel blade and preparing the surface even and smooth by using different grade sand papers including cost of all materials cost oif labour and scaffolding etc complete as per the specifications	Sqm	403.07	64.00	Rs Sixty four only
60	Providing and applying painting in two coats with plastic Emulsion paint of approved brand on wall surface to give an even approved shade after thoroughly brushing the surface, free from mortar drops and other foreign matter including preparing the surface even and sand paper smooth, cost of materials, labour, complete as per specifications and as per the directions of the Engineer in charge. (with Primer)	Sqm	254.57	101.00	Rs one hundred one only
61	Providing and applying painting in two coats with plastic Emulsion paint of approved brand on ceiling surface to give an even approved shade after thoroughly brushing the surface, free from mortar drops and other foreign matter including preparing the surface even and sand paper smooth, cost of materials, labour, complete as per specifications and as per the directions of the Engineer in charge. (with Primer)	Sqm	148.50	106.00	Rs one hundred Six only
62	Providing ACE paint to external walls of approved colour and shade over prime's coat.after brooming & cleaning the surface and applying two coats of ACE paint with cost of all material,labour,lead lift with loading unloading etc.complete as per direction of Engineer in charge of work	Sqm	251.64	202.00	Rs Two hundred two only
63	Providing and applying painting two coats (excluding priming coat) on new wood surface and / or wood basedsurface with enamel paint to give an even shade, cleaning the surface of all dirt, dust and foreign matter, sand papering including cost ofmaterials, labour, complete as per specifications.	Sqm	17.01	96.00	Rs Ninety Six only

Signature of the Contractor

Executive Engineer (Project)

SNo	Item Name	Unit	Estimate Quantity	Negotiated Rates quoted by Sri. MURTHY C N S	
				Rate in figures	Rate in words
64	Flooring with 20mm thick polished shahabad slabs using cement mortar 1:6, 25mm thick over existing cement concrete bed or top of roof laid to line and level and jointed with cement slurry mixed with pigment to match the shade of the slab including cost of materials, labour curing, polishing complete as per specifications. Ground Floor	Sqm	57.00	1362.00	Rs one thousand three hundred sixty two only
65	Flooring with 20mm thick polished shahabad slabs using cement mortar 1:6, 25mm thick over existing cement concrete bed or top of roof laid to line and level and jointed with cement slurry mixed with pigment to match the shade of the slab including cost of materials, labour, curing, polishing complete as per specifications. First Floor	Sqm	57.00	1364.00	Rs one thousand three hundred sixty four only
66	Flooring with 20mm thick polished shahabad slabs using cement mortar 1:6, 25mm thick over existing cement concrete bed or top of roof laid to line and level and jointed with cement slurry mixed with pigment to match the shade of the slab, including cost of materials, labour, curing polishing complete as per specifications Second Floor	Sqm	57.00	1366.00	Rs one thousand three hundred Sixty Six only
67	Providing and fixing M.S.grill work for windows and ventilators weighing 21kg/sqm using M.S. flats, or M.S. square rods, or combination of M.S. flats and square rods as per approved design, drawing including cutting steel sections and welding the same to required pattern with a coat of red lead primer cost of materials, fixtures, labour and HOM of machinery complete as per specifications Ground Floor	Kgs	170.10	101.00	Rs one hundred one only
68	Providing and fixing M.S.grill work for windows and ventilators weighing 21kg/sqm using M.S. flats, or M.S. square rods, or combination of M.S. flats and square rods as per approved design, drawing including cutting steel sections and welding the same to required pattern with a coat of red lead primer, cost of materials, fixtures, labour and HOM of machinery complete as per specifications First Floor	Kgs	170.10	107.00	Rs one hundred Seven only
69	Providing and fixing M.S. grill work for windows and ventilators weighing 21kg/sqm using M.S. flats or M.S. square rods, or combination of M.S. flats and square rods as per approved design, drawing including cutting steel sections and welding the same to required pattern with a coat of red lead primer, cost of materials, fixtures, labour and HOM of machinery complete as per specifications Second Floor	Kgs	170.10	113.00	Rs one hundred thirteen only.

Signature of the Contractor

Executive Engineer (Project)

SNo	Item Name	Unit	Estimate Quantity	Negotiated Rates quoted by Sri. MURTHY C N S	
				Rate in figures	Rate in words
70	Providing and applying enamel metal paint two coats(excluding priming coat) over new steel or other metal surfacebrushing to give an even shade after cleaning oil, grease, dirt and other foreign matter, including cost of materials, labour, complete as per specificat ons	Sqm	54 68	94·00	Rs Ninety four only
71	Providing and fixing in position aluminium windows and ventilators as per approved drawings with sliding shutters using threetrack window frame of size 92x31 75mm bottom sect on 1 3mm thick weight 1.07kg/m, sides and top sections 1 3 mm, thick, we ght 0 933kg/m shutter frame section compris ng top and bottom sect on of size40mmx18mm wall thickness 1 25mm weight 0 417 kg /m shutter sideouter 40mmx18mm wall thickness 1 25mm weight 0 417 kg/m shutterinterlock section 40mmx26 7mm wall th ckness 1.1 mm thick weight 0.469 kg/m, the shutters mounted on nylon rollers with approved qualityof fixtures such as aluminium handles tower bolts etc , providing andfixing 5 5mm thick plain glass for shutters fitted with rubber beading allaluminium sections including cutting to required length, joints mitredsubd viding the frame tenonned and rivetted In the assembled frame,stiffened with end clips for corners, angles etc , and fixed to the walls,l ntels, floor beams/ci.ls as the case may be, with necessary steelscrews, raul plugs or teak wood gatties including cutting masonry orconcrete and making good the original surface using cement	Sqm	8 10	4877·00	Rs Four thousand Eight hundred Seventy Seven only
72	Providing and fixing in position aluminium w ndows and ventilators as per approved drawings with sliding shutters using threetrack window frame of size 92x31 75mm bottom section 1 3mm thick,weight 1.07kg/m; sides and top sections 1.3 mm, thick, weight 0 933kg/m shutter frame section comprising top and bottom section of size40mmx18mm wall thickness 1 25mm we ght 0 417 kg /m shutter sideouter 40mmx18mm wal thickness 1 25mm we ght 0 417 kg/m, shutterinterlock section 40mmx26 7mm wall thickness 1 1 mm thick, weight 0.469 kg/m, the shutters mounted on nylon rollers with approved qualityof fixtures such as aluminium handles tower bolts etc ; providing andfixing 5 5mm thick plain glass for shutters fitted with rubber bead ng allaluminium sections including cutting to required length jo nts mitredsubd viding the frame tenonned and r vetted, in the assemb ed frame,stiffened with end clips for corners angles etc., and fixed to the walls,l ntels, floor beams/cills as the case may be, with necessary steelscrews, raul plugs or teak wood gatties including cutting masonry orconcrete and making good the original surface using cement	Sqm	8 10	4883·00	Rs Four thousand Eight hundred Eighty three only

SNo	Item Name	Unit	Estimate Quantity	Negotiated Rates quoted by Sri. MURTHY C N S	
				Rate in figures	Rate in words
73	Providing and fixing in position aluminium windows and ventilators as per approved drawings with sliding shutters using threetrack window frame of size 92x31.75mm bottom section 1 3mm thick,weight 1 07kg/m; sides and top sections 1 3 mm, thick, weight 0 933kg/m shutter frame section comprising top and bottom section of size40mmx18mm, wall thickness 1 25mm weight 0 417 kg /m. shutter sideouter 40mmx18mm. wall thickness 1 25mm weight 0 417 kg/m, shutterinterlock section 40mmx26 7mm wall thickness 1 1 mm thick, weight 0 469 kg/m. the shutters mounted on nylon rollers with approved qualityof fixtures such as aluminium handles tower bo ts etc , providing andfixing 5 5mm thick plain glass for shutters fitted with rubber beading a laluminium sections including cutting to required length, joints mitredsubdividing the frame tenonned and rivetted, in the assembled frame,stiffened with end clips for corners, ang es etc , and fixed to the walls,lintels, floor beams/cills as the case may be, with necessary steelscrews, raul plugs or teak wood gatties including cutting masonry orconcrete and mak ng good the original surface using cement	Sqm	8 10	4889 00	Rs Four thousand Eight hundred Eighty nine only
74	Fixtures Providing and fixing of Door locking arrangements	Each	3 00	709·00	Rs Seven hundred nine only
75	Providing and fixing of Handles powder coated 150mm	Each	6 00	63 00	Rs Sixty three only
76	Providing and fixing of Hinges 5" heavy duty	Each	15 00	41·00	Rs Forty one only
77	Providing and fixing of Hold fasts MS	Each	3.00	43.00	Rs Forty three only
78	Providing and fixing of Tower bolt 300mm long	Each	6.00	130.00	Rs one hundred thirty only
79	SECOND FLOOR - Dismantling of existing structures like culverts,bridges, retaining wal s and other structure comprising of masonry, cementconcrete, wood work, steel work, including T&P and scaffolding wherevernecessary sorting the dismantled material, d.sposal of unserviceablematerial and stacking the serviceable material with all lifts complete asper specifications Dismantling brick/T e work B In cement mortar	Cum	34 27	275.00	Rs Two hundred Seventy five only

Signature of the Contractor

Executive Engineer (Project)

SNo	Item Name	Unit	Estimate Quantity	Negotiated Rates quoted by Sri. MURTHY C N S	
				Rate in figures	Rate in words
80	Dismantling of existing structures like culverts, bridges, retaining walls and other structure comprising of masonry, cement concrete, wood work, steel work, including T&P and scaffolding wherever necessary, sorting the dismantled material, disposal of unserviceable material and stacking the serviceable material with all lifts complete as per specifications Lime /Cement Concrete. I. By Manual Means :B. Cement Concrete Grade M-15 & M 20.	Cum	2.73	420.00	Rs Four hundred twenty only
81	Providing and laying in position reinforced cement concrete of design mix M25 with OPC cement @ 340kgs, with 20mm and down size graded granite metal coarse aggregates @0 70cum and fine aggregtes @ 0.47cum, with superplastisiser @3lts confirming to IS9103-1999 Reaffirmed-2008, machine mixed, concrete laid in layers not exceeding 15 cms thick, vibrated for all works inground floor level for roof slabs, staircase, lintles retaining walls, return walls, walls (any thickness) including attached plasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window cills fillets etc , including cost of all materials, labour, HOM of machinery, curing, complete as per specifications.	Cum	54 21	7327.00	Rs Seven thousand three hundred twenty Seven only
82	Providing and laying cement concrete using 20mm and down size granite coarse aggregates and fine aggregares of ready mixed concrete for RCC works laid in 15 cms thick layers and well compated including vibrating, curing,etc , with all lead and lifts etc complete(exclusive of cost of steel and fabricaton charges) Ready Mixed Cement Concrete for Beams, Staircase and Roof with M-25	Cum	217 58	7177.00	Rs Seven thousand one hundred Seventy Seven only
83	Providing and laying in Mat for RCC roof at below the steel for avoiding concrete cement slurry as per the requirement of Engineer incharge.	Sqm	973 25	73.00	Rs Seventy three only
84	Providing and laying in position reinforced cement concrete of design mix M20 with OPC cement @ 24kgs, with 12mm and down size graded granite metal coarse aggregates @0.5175cum and fine aggregtes @ 0 345cum, with superplastsiser @0 225lts, machine mixed, well compacted for plain chajja of 7 5 cms. average thickness, upto ground floor level, including cost of all materials, labour, HOM of machinery, finishing, curing, complete as per specifications.	Sqm	21 06	516.00	Rs Five hundred Sixteen only
85	Providing and removing Centering, shuttering, strutting, propping etc., for columns, pillars, piers, abutments, post and struts, square / rectangular / polygon in plan including cost of materials, labour complete as per specification and directions of the Engineer in charge	Sqm	468 00	433.00	Rs Four hundred thirty three only.

Signature of the Contractor

Executive Engineer (Project)

SNo	Item Name	Unit	Estimate Quantity	Negotiated Rates quoted by Sri. MURTHY C N S	
				Rate in figures	Rate in words
86	Providing and removing centering, shuttering, strutting propping etc , and removal of form work for flat surface such as roofs land ngs balconies and likes thickness upto 200 mm including cost of all materials labour complete as per specifications upto 3 5M from Ground level	Sqm	838 19 ✓	374 00	Rs Three hundred swenty four only
87	Providing & removing centering shuttering,strutting, propping etc., and removal of form work for s des & soffits of beams beam haunch ngs, cantilever girders, bresumers and lintels not exceeding 1m in depth including cost of all materials, labour complete as per specifications.	Sqm	716 36 ✓	309 00 ✓	Rs Three hundred Nine only
88	Providing and removing centering, shuttering, strutting,propping etc . for chajjas,corbalsetc., including edges incluidng cost of all materials, labour complete as per spec fications Second F loor	Sqm	21.06 ✓	324 00	Rs Three hundred twenty four only
89	Provid ng and removing centering, shuttering, strutting, propping etc., and removal of form work for Stairs (exclud ng landing) except spira, sta rcase including cost of all materia s labour complete as per specif caiton	Sqm	34 74 ✓	565 00	Rs Five hundred Sixty five only
90	Providing TMT Steel Reinforcement for R C.C work including stra ghtening, cutting, bending, hooking, placing in position, lapp ng and / or welding wherever required, tying with binding wire and anchoring to the adjoin ng members wherever necessary comp ete as per design (aps and wastage shall not be measured and pa d) cost of materials, labour, HOM of machinery complete as per specifications TMT Bars Fe 500	MT	32 58 ✓	66244 00	Rs Sixty Six thousand two hundred fifty four only
91	Providing and constructing precast concrete Solid Blocks with compressive strength not less than 3.5 Newton per sqm with cement mortar 1.4 masonry (quion, jamb closer blocks) with Solid Concrete B ocks of size (40x20x20) cms confirming to I.S 2185/1965 in S uperstructure including cost of all materials, labour charges, scaffolding, curing complete as per specifications	Sqm	1064 33 ✓	1190 00	Rs one thousand one hundred Ninety only
92	Providing 12mm thick cement plaster in single coat with cement mortar 1:3, to ceiling including round ng off corners wherever requ red smooth rendering,, Providing and removing scaffolding, including cost of materials, labour, lead, ift, curing complete as per specifications and direction of the Engineer in charge Providing Lime rendering for Plastering to Ceiling includ ng cost of materials, labour, cur ng complete as per specification	Sqm	832 28 ✓	258 00	Rs Two hundred fifty Eight only

Signature of the Contractor

Executive Engineer (Project)

SNo	Item Name	Unit	Estimate Quantity	Negotiated Rates quoted by Sri. MURTHY C N S	
				Rate in figures	Rate in words
93	Providing 18mm thick cement plaster in single coat with cement mortar 1:4, to brick masonry including rounding off corners wherver required smooth rendering, : Providing lime rendering for plastering to wall and ceiling and Providing and removing scaffolding cost of materials, labour, curing complete as per specifications, direction of the Engineer in charge for Inside Plastering	Sqm	1224.59	290.00	Rs Two hundred Ninety only
94	Providing 18mm thick cement plaster in single coat with cement mortar 1:4, to brick masonry including rounding off corners wherver required smooth rendering, : Providing and removing scaffolding, cost of materials labour, curing complete as per specifications and direction of the Engineer in charge.for Outside Plastering	Sqm	832.53	273.00	Rs Two hundred Seventy three only
95	Flooring with 20mm thick polished shahabad slabs using cement mortar 1:6, 25mm thick over existing cement concrete bed or top of roof laid to line and level and jointed withcement slurry mixed with pigment to match the shade of the slab, including cost of materials, labour, curing, polishing complete as per specifications	Sqm	1044.73	1366.00	Rs one thousand three hundred Sixty Six only
96	Providing and fixing M S grill work for windows and ventilators weighing 21kg/sqm using M.S flats, or M S square rods, or combination of M S flats and square rods as per approved design, drawing including cutting steel sections and welding the same to required pattern with a coat of red lead primer, cost of materials, fixtures, labour and HOM of machinery complete as per specifications.	Kgs	2083.83	113.00	Rs one hundred thirteen only
97	Providing and applying enamel metal paint two coats(excluding priming coat) over new steel or other metal surfacebrushing to give an even shade after cleaning oil, grease, dirt and other foreign matter, including cost of materials, labour, complete as per specifications	Sqm	99.23	94.00	Rs Ninety four only

Signature of the Contractor

Executive Engineer (Project)

SNo	Item Name	Unit	Estimate Quantity	Negotiated Rates quoted by Sri. MURTHY C N S	
				Rate in figures	Rate in words
98	Providing and fixing in position aluminium windows and ventilators as per approved drawings with sliding shutters using threetrack window frame of size 92x31 75mm bottom section 1.3mm thick,weight 1 07kg/m; sides and top sections 1.3 mm, thick, weight 0 933kg/m shutter frame section comprising top and bottom section of size40mmx18mm, wall thickness 1.25mm weight 0.417 kg./m shutter sideouter 40mmx18mm wall thickness 1 25mm weight 0 417 kg/m shutterinterlock section 40mmx26 7mm wall thickness 1.1 mm. thick, weight 0 469 kg/m, the shutters mounted on nylon rollers with approved qualityof fixtures such as aluminium handles tower bolts etc ; providing andfixing 5 5mm thick plain glass for shutters fitted with rubber beading allaluminium sections including cutting to required length, joints mitredsubdividing the frame tenonned and rivetted in the assembled frame,stiffened with end clips for corners angles etc., and fixed to the walls,lintels, floor beams/cills as the case may be, with necessary steelscrews, raul plugs or teak wood gatties including cutting masonry orconcrete and making good the original surface using cement	Sqm	99 23	4889·00	Rs Four thousand Eight hundred Eighty nine only
99	Fixing of door frames in an existing opening including embedding frame in floor and walls after cutting masonary for holdfasts for embedding holdfast in cement concrete 1 3 6 of 20mm and downsize granite metal painting two coats of coal tar to sides of frame,making good the damages to walls and floor as required and disposal of the debnes with lead upto 50 m including cost of materials, labour, complete as per specifications Pg No 57,Item No9 80	Sqm	13 00	1202·00	Rs one thousand two hundred two only
100	Providing Honne wood frames of doors, windows, clerestory windows, ventilators and other frames, wrought, framed or assembled including making plaster groves (excluding cost of cement concrete and side clamps), but including cost of materials, labour, HOM of machineries complete as per specifications	Cum	0 59	121793·00	Rs one Lakh twenty one thousand Seven hundred ninety three only .
101	Providing and fixing in position fully panelled Honne Wood shutters for doors, styles and rails of 40mm thick with bottom and lock rails 180mm wide top rail and styles 100mm wide as per drawing and panels of 25mm thick including cost of materials, labour, HOM of machineries Complete as per Specifications.	Sqm	24 70	5376·00	Rs Five thousand three hundred Seventy Six only
102	Providing applying two coats of wall putty to inside plastered walls and ceiling using white cement putty Scrapping and levelling the surface using,steel blade and preparing the surface even and smooth by using different grade sand papers including cost of all materials cost oif labour and scaffolding etc complete as per the specifications	Sqm	2056 87	64·00	Rs Sixty four only

Signature of the Contractor

Executive Engineer (Project)

SNo	Item Name	Unit	Estimate Quantity	Negotiated Rates quoted by Sri. MURTHY C N S	
				Rate in figures	Rate in words
103	Providing and applying painting two coats (excluding priming coat) on new wood surface and / or wood basedsurface with enamel paint to give an even shade, clean ng the surface of all dirt, dust and fore gn matter, sand papering ncluding cost ofmaterials, labour complete as per specifications	Sqm	73 71	96.00	Rs Ninety Six only
104	Providing and applying pa nting in two coats with plastic Emulsion paint of approved brand on wall surface to give an even approved shade after thoroughly brushing the surface free from mortar drops and other foreign matter including preparing the surface even and sand paper smooth, cost of materials labour, complete as per specifications and as per the directions of the Engineer in charge (with Primer)	Sqm	1273 64	101.00	Rs one hundred one only
105	Providing and applying painting in two coats with plastic Emulsion paint of approved brand on Ceiling surface to give an even approved shade after thoroughly brushing the surface, free from mortar drops and other foreign matter including preparing the surface even and sand paper smooth, cost of materials, labour, complete as per specifications and as per the direct ons of the Engineer in charge (with Primer)	Sqm	832 28	106.00	Rs one hundred Six only
106	Prov d ng ACE pa nt to external walls of approved colour and shade over prime's coat after brooming & cleaning the surface and applying two coats of ACE pa nt with cost of all material,labour,lead lift with oad ng unloading etc complete as per direction of Engineer in charge of work.	Sqm	832 53	202.00	Rs Two hundred two only
107	Providing and aying in position plain cement concrete of mix M20 with OPC cement @ 300kgs, with 20mm and down s ze graded granite metal coarse aggregates @0 69cum and fine aggregtes @ 0 43cum, with superplastisiser @3lts confirming to IS9103-1999 Reaff rmed-2008, machine mixed, concrete laid in layers not exceeding 15 cms thick, well compacted, in fo.undation,plinth and cills, including cost of all materials, labour, HOM of machinery, curing comp ete as per specificat ons	Cum	72 99	6702.00	Rs Six thousand Seven hundred two only
108	Extra for use of water proofing compound in cement concrete of mix 1:1 5 3 @ 1kg of compound per Bag of cement	Cum	72 99	224.00	Rs Two hundred twenty four only.
109	Fixtures Providing and fixing of Door locking arrangements	Each	13 00	709.00	Rs Seven hundred nine only.
110	Providing and fixing of Handles powder coated 150mm	Each	13 00	63.00	Rs Sixty three only

SNo	Item Name	Unit	Estimate Quantity	Negotiated Rates quoted by Sri. MURTHY C N S	
				Rate in figures	Rate in words
111	Providing and fixing of Hinges 5" heavy duty	Each	100.00	41·00	Rs Fourty one only
112	Providing and fixing of Hold fasts MS	Each	13.00	43·00	Rs Fourty three only
113	Providing and fixing of Tower bolt 300mm long	Each	30.00	130·00	Rs one hundred thirty only.
114	TOILET BLOCK WITH STAIRCASE (GENTS)- Earth work excavation for foundation of buildings, water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, in Hard soil not exceeding 1.5m in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50m after breaking of clods complete as per specification	Cum	94.17	317·00	Rs Three hundred Seventeen only
115	Filling available excavated earth (excluding rock) insides of foundations upto plinth in layers not exceeding 20cms. In depth, compacting each deposited layer by ramming after watering with a lead upto 50m. And lift upto 1.5m including cost of all labour complete as per specifications.	Cum	53.79	142·00	Rs one hundred forty two only.
116	Transportation of excavated earth by mechanical means including loading and unloading with a lead of 20 kmtr and dispersing the same as directed	Cum	56.50	128·00	Rs one hundred twenty eight only
117	Providing and laying in position Plain Cement Concrete of mix 1:3:6 with OPC cement @ 220kgs ,with 40mm and down size graded granite metal coarse aggregates @ 0 .892 cum and fine aggregates @ 0.465cum machine mixed, concrete laid in layers not exceeding 15 cms thick, well compacted, in foundation including cost of all materials,labour, HOM of machinery ,curing complete as per specifications.	Cum	7.18	5754·00	Rs Five thousand Seven hundred fifty four only
118	Providing and constructing granite / trap / basalt Size Stone Masonry in cement mortar 1:6, stone hammered dressed in courses not less than 20 cms high, bond stones at two m. apart in each course including cost of maerials, labour, curing Complete as per specifications.	Cum	13.73	4544·00	Rs Four thousand five hundred forty four only

Signature of the Contractor

Executive Engineer (Project)

SNo	Item Name	Unit	Estimate Quantity	Negotiated Rates quoted by Sri. MURTHY C N S	
				Rate in figures	Rate in words
119	Providing and laying in position reinforced cement concrete of design mix M25 with OPC cement @ 340kgs, with 20mm and down size graded granite metal coarse aggregates @0.70cum and fine aggregtes @ 0.47cum, with superplastisiser @3lts confirming to IS9103-1999 Reaffirmed-2008, machine mixed, concrete laid in layers not exceeding 15 cms thick, vibrated for all works in foundation plinth for roof slabs, staircase, lintles, retaining walls, return walls, walls (any thickness) including attached plasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window cills, fillets etc , including cost of all materials, labour, HOM of machinery, curing, complete as per specifications.	Cum	19.22	7208.00	Rs Seven thousand two hundred Eight only
120	Providing and laying in position reinforced cement concrete of design mix M25 with OPC cement @ 340kgs, with 20mm and down size graded granite metal coarse aggregates @0.70cum and fine aggregtes @ 0.47cum, with superplastisiser @3lts confirming to IS9103-1999 Reaffirmed-2008, machine mixed, concrete laid in layers not exceeding 15 cms thick, vibrated for all works in ground floor level for roof slabs, staircase, lintles, retaining walls, return walls, walls (any thickness) including attached plasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window cills, fillets etc., including cost of all materials, labour, HOM of machinery, curing, complete as per specifications. Ground Floor	Cum	11.38	7208.00	Rs Seven thousand two hundred Eight only
121	Providing and laying in position reinforced cement concrete of design mix M25 with OPC cement @ 340kgs, with 20mm and down size graded granite metal coarse aggregates @0.70cum and fine aggregtes @ 0.47cum, with superplastisiser @3lts confirming to IS9103-1999 Reaffirmed-2008, machine mixed, concrete laid in layers not exceeding 15 cms thick, vibrated for all works in ground floor level for roof slabs, staircase, lintles, retaining walls, return walls, walls (any thickness) including attached plasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window cills, fillets etc., including cost of all materials, labour, HOM of machinery, curing, complete as per specifications. First Floor	Cum	8.92	7267.00	Rs Seven thousand two hundred Sixty Seven only

Signature of the Contractor

Executive Engineer (Project)

SNo	Item Name	Unit	Estimate Quantity	Negotiated Rates quoted by Sri. MURTHY C N S	
				Rate in figures	Rate in words
122	Providing and laying in position reinforced cement concrete of design mix M25 with OPC cement @ 340kgs, with 20mm and down size graded granite metal coarse aggregates @0.70cum and fine aggregtes @ 0.47cum, with superplastisiser @3lts confirming to IS9103-1999 Reaffirmed-2008, machine mixed, concrete laid in layers not exceeding 15 cms thick, vibrated for all works in ground floor level for roof slabs, staircase, lintles, retaining walls, return walls, walls (any thickness) including attached plasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window cills, fillets etc., including cost of all materials, labour, HOM of machinery, curing, complete as per specifications. Second Floor	Cum	9.46	7327.00	Rs Seven thousand three hundred twenty Seven only
123	Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for vertical surface such as walls at any thickness, including attached pilasters, buttresses, plinth and string courses cost of all materials, labour complete as per specificaitons.	Sqm	40.23	337.00	Rs Three hundred thirty Seven only
124	Providing and laying cement concrete using 20mm and down size granite coarse aggregates and fine aggregares of ready mixef concrete for RCC works laid in 15 cms thick layers and well compated including vibrating, curing,etc., with all lead and lifts etc complete(excluisive of cost of steel and fabrication charges) Ready Mixed Cement Concrete for Beams, Staircase and Roof with M-25	Cum	36.07	7177.00	Rs Seven thousand one hundred Seventy Seven only
125	Providing and removing Centering, shuttering, strutting, propping etc., for columns, pillars, piers, abutments, post and struts, square / rectangular / polygon in plan including cost of materials, labour complete as per specification and directions of the Engineer in charge. Ground Floor	Sqm	27.00	421.00	Rs Four hundred twenty one only
126	Providing and removing Centering, shuttering, strutting, propping etc., for columns, pillars, piers, abutments, post and struts, square / rectangular / polygon in plan including cost of materials, labour complete as per specification and directions of the Engineer in charge. First Floor	Sqm	43.50	427.00	Rs Four hundred twenty Seven only
127	Providing and removing Centering, shuttering, strutting, propping etc., for columns, pillars, piers, abutments, post and struts, square / rectangular / polygon in plan including cost of materials, labour complete as per specification and directions of the Engineer in charge. Second Floor	Sqm	43.50	433.00	Rs Four hundred thirty three only

Signature of the Contractor

Executive Engineer (Project)

SNo	Item Name	Unit	Estimate Quantity	Negotiated Rates quoted by Sri. MURTHY C N S	
				Rate in figures	Rate in words
128	Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for flat surface such as roofs landings balconies and likes thickness upto 200 mm including cost of all materials labour complete as per specifications upto 3.5M from Ground level. Ground Floor	Sqm	63.70	362.00	Rs Three hundred Sixty two only
129	Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for flat surface such as roofs landings balconies and likes thickness upto 200 mm including cost of all materials labour complete as per specifications upto 3.5M from Ground level. First Floor	Sqm	63.70	368.00	Rs Three hundred Sixty Eight only
130	Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for flat surface such as roofs landings balconies and likes thickness upto 200 mm including cost of all materials labour complete as per specifications upto 3.5M from Ground level. Second Floor	Sqm	63.70	374.00	Rs Three hundred Seventy four only
131	Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for sides and soffits of beams, beam haunchings, cantilever girders, bressumers and lintles exceeding 1 m in depth incluidng cost of all materials, labour complete as per specifications. Ground Floor	Sqm	26.16	297.00	Rs Two hundred Ninety Seven only
132	Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for sides and soffits of beams, beam haunchings, cantilever girders, bressumers and lintles exceeding 1 m in depth incluidng cost of all materials, labour complete as per specifications. First Floor	Sqm	36.80	303.00	Rs Three hundred three only
133	Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for sides and soffits of beams, beam haunchings, cantilever girders, bressumers and lintles exceeding 1 m in depth incluidng cost of all materials, labour complete as per specifications. Second Floor	Sqm	36.80	309.00	Rs Three hundred nine only
134	Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for Stairs (excluding landing) except spiral staircase including cost of all materials, labour completeas per specificaiton. Ground Floor	Sqm	26.67	553.00	Rs Five hundred fifty three only
135	Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for Stairs (excluding landing) except spiral staircase including cost of all materials, labour completeas per specificaiton. First Floor	Sqm	26.67	559.00	Rs Five hundred fifty nine only
136	Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for Stairs (excluding landing) except spiral staircase including cost of all materials, labour completeas per specificaiton. Second Floor	Sqm	26.67	565.00	Rs Five hundred Sixty five only.

Signature of the Contractor

Executive Engineer (Project)